The use of drawings by the Customer acts as an agreement to the following statements. The Customer must not use the drawings if it does not agree with any of the following statements:

All drawings are based upon site information supplied by third parties and as such their accuracy cannot be guaranteed. All features are approximate and subject to clarification by a detailed topographical survey, statutory service enquiries and confirmation of the legal boundaries. Do not scale the drawings. Figured dimensions must be used in all cases. All dimensions must be checked on site. Any discrepancies must be reported in writing to Colour-UDL before proceeding. All drawings are copyright protected. Refer to full Terms & Conditions at www.colour-udl.com

Hardworks

- Tarmac Road Surface with PCC Road Kerb
- Precast concrete textured paving flags
- Coloured Tarmac for Cycle Lane to be Light Buff colour or similar with PCC Pin Kerb Edging
- Compacted aggregate surface
- Cobble / Setts to Edge of Pond / Swale
- Blister Tactile Paving to Pedestrian Crossing
- Corduroy Tactile Paving to Steps

Softworks

- Existing Woodland Area
- Existing Trees to be Retained
- Existing Trees to be Removed
- Existing Hedge to be Retained
- Existing Hedge to be Removed
- Proposed Trees
- Proposed Woodland Planting
- Proposed Wetland Planting (permanent pond area)
- Proposed Hedge Planting
- Proposed Grassland
- Proposed Wildflower Meadow

Landscape Features

- Proposed Timber Bench
- Proposed Steps with timber handrail
- Proposed Retaining Wall Gabion type with local aggregate infill
- Proposed Estate Railings
- Proposed Gate

Landform

- Existing Contour
- Proposed Contour
- (106.5) Existing Level
- 107.5 Proposed Level

Site

- Area of Weymouth Road Frontage

Rev	Amendments	Date	Drwn	Chkd
03	Amends made to western attenuation basin as volume required was reduced. Retaining walls omitted from this area.	01.03.16	AH	SWM
02	Issued for Planning	23.02.16	AH	SWM
01	First Issue	19.02.16	SWM	CT

Project
Chapelgarth, Sunderland

Drawing Title
Detail Design of Weymouth Road Frontage Central

Project No.
1515

Scale @ A0
1:250

Project Status
Planning

Drawing No.
L-1515-GAP-004

Revision
03

London 0207 38 78 560
Newcastle 0191 24 24 224
colour-udl.com

colour urban design limited